

NETAJI SUBHAS INSTITUTE OF TECHNOLOGY
AZAD HIND FAUJ MARG: SECTOR-3, DWARKA
NEW DELHI-110075.

No. F. 201(1796/MDC/09-10/E.Cell/NSIT/

Dated: 05.05.2009

NOTICE INVITING QUOTATION

Sealed item rate quotations are hereby invited on behalf of Board of Governors, NSIT, New Delhi from the appropriate class of CPWD, M.E.S., Railways & Deptt. of Telecommunication and specialized agencies having valid TIN No. & DVAT clearance certificate for the following work so as to reach the office of undersigned up to 3.00 P.M. on 12.05.2009. Quotations shall be opened on the same day at 3.30 P.M.:

Name of work: A.R. & M.O. NSIT Campus during 2009-10.

Sub-Head: Provision of Push cocks, Raw water Supply and Misc. water supply works at Boys Hostels & MSH at NSIT complex

Estimated Cost: Rs. 1,83,927.00

TERMS & CONDITIONS:

1. Time allowed: 45 days.
2. Specifications: CPWD Specifications 1996, Vol-I to VI with upto date correction slips and manufacturer's recommendations.
3. Schedule of Quantity: As per Annexure-A.
4. T &P: No T & P shall be issued from NSIT.

EXECUTIVE ENGINEER (C)/M

NETAJI SUBHAS INSTITUTE OF TECHNOLOGY
AZAD HIND FAUJ MARG: SECTOR-3
DWARKA, NEW DELHI-110078

SCHEDULE OF QUANTITY

Name of Work: A.R. & M.O. NSIT Campus during 2009-10.

Sub Head : Provision of Push cocks, Raw water Supply and Misc. water supply works at Boys Hostels & MSH at NSIT complex.

S. No.	Description	Unit	Rate	Qty.	Amount	
1	Providing and fixing G.I. pipes complete with G.I. fittings and clamps, including cutting and making good the walls etc.					
	Internal work – Exposed on wall.					
a)	15 mm dia. nominal bore	metre		150.00		
b)	20 mm dia. nominal bore	metre		150.00		
c)	25 mm dia. nominal bore	metre		150.00		
2	Making connection of G.I. distribution branch with G.I. main of following sizes by providing and fixing tee, including cutting and threading the pipe etc. complete :					
a)	25 to 40 mm nominal bore	each		50.00		
3	Providing and fixing gun metal gate valve with C.I. wheel of approved quality (screwed end) :					
a)	25 mm nominal bore	each		48.00		
4	Painting G.I. pipes and fittings with synthetic enamel white paint over a ready mixed priming coat, both of approved quality for new work :					
a)	15 mm diameter pipe.	Metre		150.00		
b)	20 mm diameter pipe.	Metre		150.00		
c)	25 mm diameter pipe.	metre		150.00		

5	Providing and fixing G.I. Union in G.I. pipe including cutting and threading the pipe and making long screws etc. complete (New work)					
a)	15 mm nominal bore	each		28.00		
b)	20 mm nominal bore	each		32.00		
c)	25 mm nominal bore	each		32.00		
6	Providing and fixing PTMT, push cock of approved quality and colour					
a)	15 mm nominal bore, 98mm long. Weighing not less than 75 gms.	each		185.00		
b)	15 mm nominal bore, 80mm long. Weighing not less than 46 gms.	each		431.00		
7	Providing and fixing PTMT Ball cock of approved quality, colour and make complete with Epoxy coated aluminium rod with L.P./ H.P.H.D. plastic ball.					
a)	20 mm nominal bore, 120 mm long. Weighing not less than 198 gms.	each		10.00		
b)	25 mm nominal bore, 152mm long. Weighing not less than 440 gms	each		35.00		
8	Providing and fixing PTMT extension nipple for water tank pipe, fittings of approved quality and colour.					
a)	20mm nominal bore. Weighing not less than 40gms.	each		17.00		
b)	25mm nominal bore. Weighing not less than 62 gms.	each		17.00		
9	Taking out of existing CP/PTMT/ Brass bibcock & submission of same in the store.	each		616.00		
				Total		

EXECUTIVE ENGINEER (C)/M